



# Local Government Energy Audit: Energy Audit Report



Copyright ©2016 TRC Energy Services. All rights reserved.

Reproduction or distribution of the whole, or any part of the contents of this document without written permission of TRC is prohibited. Neither TRC nor any of its employees makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any data, information, method, product or process disclosed in this document, or represents that its use will not infringe upon any privately-owned rights, including but not limited to, patents, trademarks or copyrights.

**Booster Station**

**Township of Livingston**

55 North Hillside Avenue

Livingston, NJ 07039

June 20, 2018

Final Report by:

**TRC Energy Services**

## Disclaimer

---

The intent of this energy analysis report is to identify energy savings opportunities and recommend upgrades to the facility's energy using equipment and systems. Approximate savings are included in this report to help make decisions about reducing energy use at the facility. This report, however, is not intended to serve as a detailed engineering design document. Further design and analysis may be necessary in order to implement some of the measures recommended in this report.

The energy conservation measures and estimates of energy savings have been reviewed for technical accuracy. However, estimates of final energy savings are not guaranteed, because final savings may depend on behavioral factors and other uncontrollable variables. TRC Energy Services (TRC) and New Jersey Board of Public Utilities (NJBPU) shall in no event be liable should the actual energy savings vary.

Estimated installation costs are based on TRC's experience at similar facilities, pricing from local contractors and vendors, and/or cost estimates from *RS Means*. The owner of the facility is encouraged to independently confirm these cost estimates and to obtain multiple estimates when considering measure installations. Since actual installed costs can vary widely for certain measures and conditions, TRC and NJBPU do not guarantee installed cost estimates and shall in no event be held liable should actual installed costs vary from estimates.

New Jersey's Clean Energy Program (NJCEP) incentive values provided in this report are estimates based on program information available at the time of the report. Incentive levels are not guaranteed. The NJBPU reserves the right to extend, modify, or terminate programs without prior notice. The owner of the facility should review available program incentives and eligibility requirements prior to selecting and installing any energy conservation measures.

# Table of Contents

---

<b>1</b>	<b>Executive Summary</b> .....	<b>1</b>
1.1	Facility Summary .....	1
1.2	Your Cost Reduction Opportunities.....	1
	Energy Conservation Measures.....	1
	Energy Efficient Practices .....	2
	On-Site Generation Measures.....	2
1.3	Implementation Planning.....	3
<b>2</b>	<b>Facility Information and Existing Conditions</b> .....	<b>4</b>
2.1	Project Contacts .....	4
2.2	General Site Information.....	4
2.3	Building Occupancy .....	4
2.4	Building Envelope .....	5
2.5	On-Site Generation.....	5
2.6	Energy-Using Systems .....	6
	Lighting System .....	6
	Heating System .....	6
	Motors .....	7
2.7	Water-Using Systems .....	7
<b>3</b>	<b>Site Energy Use and Costs</b> .....	<b>8</b>
3.1	Total Cost of Energy .....	8
3.2	Electricity Usage .....	9
3.3	Benchmarking.....	10
3.4	Energy End-Use Breakdown .....	12
<b>4</b>	<b>Energy Conservation Measures</b> .....	<b>13</b>
4.1	Recommended ECMs .....	13
4.1.1	Motor Upgrades .....	14
	ECM 1: Premium Efficiency Motors .....	14
4.1.2	Electric Unitary HVAC Measures .....	15
	ECM 2: Install High Efficiency Heat Pumps.....	15
<b>5</b>	<b>Energy Efficient Practices</b> .....	<b>16</b>
	Reduce Air Leakage .....	16
	Close Doors and Windows .....	16
	Develop a Lighting Maintenance Schedule .....	16
<b>6</b>	<b>On-Site Generation Measures</b> .....	<b>17</b>
6.1	Photovoltaic.....	17
6.2	Combined Heat and Power .....	19
<b>7</b>	<b>Demand Response</b> .....	<b>20</b>
<b>8</b>	<b>Project Funding / Incentives</b> .....	<b>21</b>

8.1	SmartStart .....	22
8.2	Direct Install .....	23
<b>9</b>	<b>Energy Purchasing and Procurement Strategies .....</b>	<b>24</b>
9.1	Retail Electric Supply Options.....	24
9.2	Retail Natural Gas Supply Options .....	24

Appendix A: Equipment Inventory & Recommendations

Appendix B: ENERGY STAR® Statement of Energy Performance

# Table of Figures

---

Figure 1 – Previous 12 Month Utility Costs..... 1

Figure 2 – Potential Post-Implementation Costs ..... 1

Figure 3 – Summary of Energy Reduction Opportunities ..... 2

Figure 4 – Project Contacts ..... 4

Figure 5 - Building Schedule..... 4

Figure 6 - Utility Summary ..... 8

Figure 7 - Energy Cost Breakdown ..... 8

Figure 8 - Electric Usage & Demand..... 9

Figure 9 - Electric Usage & Demand..... 9

Figure 10 - Energy Use Intensity Comparison – Existing Conditions..... 10

Figure 11 - Energy Use Intensity Comparison – Following Installation of Recommended Measures ..... 10

Figure 12 - Energy Balance (% and kBtu/SF) ..... 12

Figure 13 – Summary of Recommended ECMs..... 13

Figure 14 - Summary of Motor Upgrade ECMs..... 14

Figure 15 - Summary of Unitary HVAC ECMs..... 15

Figure 16 - Photovoltaic Screening ..... 18

Figure 17 - Combined Heat and Power Screening ..... 19

Figure 18 - ECM Incentive Program Eligibility..... 21

# I EXECUTIVE SUMMARY

The New Jersey Board of Public Utilities (NJBPUB) has sponsored this Local Government Energy Audit (LGEA) Report for Booster Station.

The goal of an LGEA report is to provide you with information on how your facility uses energy, identify energy conservation measures (ECMs) that can reduce your energy use, and provide information and assistance to help facilities implement ECMs. The LGEA report also contains valuable information on financial incentives from New Jersey’s Clean Energy Program (NJCEP) for implementing ECMs.

This study was conducted by TRC Energy Services (TRC), as part of a comprehensive effort to assist New Jersey local governments in controlling energy costs and protecting our environment by offering a wide range of energy management options and advice.

## I.1 Facility Summary

Livingston Township Booster Station is a 360 square foot facility comprised of a mechanical equipment storage area. The only function of the facility is to store two pumps that pump well water to the high tank. The facility is heated by an electric resistance unit heater and is slab on grade construction with a brick façade, aluminum frame windows and an insulated metal door.


A thorough description of the facility and our observations are located in Section 2.

## I.2 Your Cost Reduction Opportunities


### Energy Conservation Measures

TRC evaluated two measures which together represent an opportunity for Booster Station to reduce annual energy costs by \$1,461 and annual greenhouse gas emissions by 9,428 lbs CO<sub>2</sub>e. We estimate that if all measures were implemented as recommended, the project would pay for itself in 9.5 years. The breakdown of existing and potential utility costs after project implementation are illustrated in Figure 1 and Figure 2, respectively. Together these measures represent an opportunity to reduce Booster Station’s annual energy use by 13%.

*Figure 1 – Previous 12 Month Utility Costs*



*Figure 2 – Potential Post-Implementation Costs*



A detailed description of Booster Station’s existing energy use can be found in Section 3.

Estimates of the total cost, energy savings, and financial incentives for the proposed energy efficient upgrades are summarized below in Figure 3. A brief description of each category can be found below and a description of savings opportunities can be found in Section 4.

**Figure 3 – Summary of Energy Reduction Opportunities**

Energy Conservation Measure		Recommend?	Annual Electric Savings (kWh)	Peak Demand Savings (kW)	Annual Fuel Savings (MMBtu)	Annual Energy Cost Savings (\$)	Estimated Install Cost (\$)	Estimated Incentive (\$)*	Estimated Net Cost (\$)	Simple Payback Period (yrs)**	CO <sub>2</sub> e Emissions Reduction (lbs)
<b>Motor Upgrades</b>			<b>3,143</b>	<b>0.9</b>	<b>0.0</b>	<b>\$490.29</b>	<b>\$6,936.66</b>	<b>\$0.00</b>	<b>\$6,936.66</b>	<b>14.1</b>	<b>3,165</b>
ECM 1	Premium Efficiency Motors	Yes	3,143	0.9	0.0	\$490.29	\$6,936.66	\$0.00	\$6,936.66	14.1	3,165
<b>Electric Unitary HVAC Measures</b>			<b>6,220</b>	<b>0.0</b>	<b>0.0</b>	<b>\$970.25</b>	<b>\$7,197.54</b>	<b>\$276.00</b>	<b>\$6,921.54</b>	<b>7.1</b>	<b>6,263</b>
ECM 2	Install High Efficiency Heat Pumps	Yes	6,220	0.0	0.0	\$970.25	\$7,197.54	\$276.00	\$6,921.54	7.1	6,263
<b>TOTALS</b>			<b>9,362</b>	<b>0.9</b>	<b>0.0</b>	<b>\$1,460.54</b>	<b>\$14,134.20</b>	<b>\$276.00</b>	<b>\$13,858.20</b>	<b>9.5</b>	<b>9,428</b>

\* - All incentives presented in this table are based on NJ Smart Start Building equipment incentives and assume proposed equipment meets minimum performance criteria for that program.

\*\* - Simple Payback Period is based on net measure costs (i.e. after incentives).

**Motor Upgrades** generally involve replacing older standard efficiency motors with high efficiency standard (NEMA Premium®). Motors replacements generally assume the same size motors, just higher efficiency. Although occasionally additional savings can be achieved by downsizing motors to better meet current load requirements. This measure saves energy by reducing the power used by the motors, due to improved electrical efficiency.

**Electric Unitary HVAC** measures generally involve replacing older inefficient air conditioning systems with modern energy efficient systems. New air conditioning systems can provide equivalent cooling to older air condition systems at a reduced energy cost. These measures save energy by reducing the power used by the air conditioning systems, due to improved electrical efficiency.

### Energy Efficient Practices

TRC also identified three low cost (or no cost) energy efficient practices. A facility’s energy performance can be significantly improved by employing certain behavioral or operational adjustments and by performing better routine maintenance on building systems. These practices can extend equipment lifetime, improve occupant comfort, provide better health and safety, as well as reduce annual energy and O&M costs. Potential opportunities identified at Booster Station include:

- Reduce Air Leakage
- Close Doors and Windows
- Develop a Lighting Maintenance Schedule

For details on these Energy Efficient Practices, please refer to Section 5.

### On-Site Generation Measures

TRC evaluated the potential for installing on-site generation for Booster Station. Based on the configuration of the site and its loads there is a low potential for installing any PV and combined heat and power self-generation measures.

For details on our evaluation and on-site generation potential, please refer to Section 6.

### I.3 Implementation Planning

To realize the energy savings from the ECMs listed in this report, a project implementation plan must be developed. Available capital must be considered and decisions need to be made whether it is best to pursue individual ECMs separately, groups of ECMs, or a comprehensive approach where all ECMs are implemented together, possibly in conjunction with other facility upgrades or improvements.

Rebates, incentives, and financing are available from NJCEP, as well as other sources, to help reduce the costs associated with the implementation of energy efficiency projects. Prior to implementing any measure, please review the relevant incentive program guidelines before proceeding. This is important because in most cases you will need to submit applications for the incentives prior to purchasing materials or commencing with installation.

The ECMs outlined in this report may qualify under the following program(s):

- SmartStart
- Direct Install

For facilities wanting to pursue only selected individual measures (or planning to phase implementation of selected measures over multiple years), incentives are available through the SmartStart program. To participate in this program, you may utilize internal resources, or an outside firm or contractor, to do the final design of the ECM(s) and do the installation. Program pre-approval is required for some SmartStart incentives, so only after receiving pre-approval should you proceed with ECM installation. The incentive estimates listed above in Figure 3 are based on the SmartStart program. More details on this program and others are available in Section 8.

This facility may also qualify for the Direct Install program which can provide turnkey installation of multiple measures, through an authorized network of participating contractors. This program can provide substantially higher incentives than SmartStart, up to 70% of the cost of selected measures, although measure eligibility will have to be assessed and be verified by the designated Direct Install contractor and, in most cases, they will perform the installation work.

Additional information on relevant incentive programs is located in Section 8 or: [www.njcleanenergy.com/ci](http://www.njcleanenergy.com/ci).



## 2 FACILITY INFORMATION AND EXISTING CONDITIONS

### 2.1 Project Contacts

*Figure 4 – Project Contacts*

Name	Role	E-Mail	Phone #
<b>Customer</b>			
Russell A. Jones	Deputy Township Manager	rjones@livingstonnj.org	(973) 992-5000
<b>Designated Representative</b>			
Esther Lin	Intern	intern2@livingstonnj.org	(973) 992-5000 x5305
<b>TRC Energy Services</b>			
Ignacio Badilla	Auditor	ibadilla@trcsolutions.com	(732) 855-0033

### 2.2 General Site Information

On May 18, 2017, TRC performed an energy audit at Booster Station located in Livingston, New Jersey. TRC's team met with Frank Denick to review the facility operations and help focus our investigation on specific energy-using systems.

Booster Station is a 360 square foot facility comprised of a mechanical equipment housing area. The only function of the facility is to store two pumps that pump well water to the High Tank. The facility is heated by an electric resistance unit heater and is slab on grade construction with a brick façade, aluminum frame windows and an insulated metal door. The facility was opened in 1956 and is in good overall condition.

### 2.3 Building Occupancy

The facility does not have any full-time staff and is used about once per day as maintenance staff check equipment and perform routine maintenance on the equipment.

*Figure 5 - Building Schedule*

Building Name	Weekday/Weekend	Operating Schedule
Booster Station	Weekday	No Schedule
Booster Station	Weekend	No Schedule

## 2.4 Building Envelope

The facility is slab on grade construction with brick façade and the roof is gable type with asphalt shingles. The door is insulated metal with weather stripping and is in good condition. The windows are single pane however, there are no significant sources of infiltration and the overall building air tightness is good.



## 2.5 On-Site Generation

The facility has a natural gas emergency generator that is new. The natural gas connection is only for the generator. While onsite, the keys to open the generator panel were not available to see the nameplate however, it is estimated to be a 100 kW generator.



## 2.6 Energy-Using Systems

Please see Appendix A: Equipment Inventory & Recommendations for an inventory of the facility's equipment.

### Lighting System

The interior of the building is lit by one eight foot 2 lamp T8 surface mounted fixture with 59-Watt lamps. The facility has one 20-Watt LED wall mounted area light on the exterior as well as one 30-Watt wall mounted area light. Due to the low use hours we do not recommend replacing the interior T8's.



### Heating System

The heating is provided by one 3.5 kW Dayton electric resistance unit heater (MN #UF79A). The unit heater is in good condition and is estimated to be about five years old.



## Motors

There are two booster motors pumps located at this site and they run twice per day for about three hours. According to our discussions with the Township water department, the motors hours are constant throughout the year and can be monitored from their central control system.



## 2.7 Water-Using Systems

This facility has no bathrooms or other water using systems.

### 3 SITE ENERGY USE AND COSTS

Utility data for electricity was analyzed to identify opportunities for savings. In addition, data for electricity was evaluated to determine the annual energy performance metrics for the building in energy cost per square foot and energy usage per square foot. These metrics are an estimate of the relative energy efficiency of this building. There are a number of factors that could cause the energy use of this building to vary from the “typical” energy usage profile for facilities with similar characteristics. Local weather conditions, building age and insulation levels, equipment efficiency, daily occupancy hours, changes in occupancy throughout the year, equipment operating hours, and energy efficient behavior of occupants all contribute to benchmarking scores. Please refer to the Benchmarking section within Section 3.3 for additional information.

#### 3.1 Total Cost of Energy


The following energy consumption and cost data is based on the last 12-month period of utility billing data that was provided for each utility. A profile of the annual energy consumption and energy cost of the facility was developed from this information.

*Figure 6 - Utility Summary*

Utility Summary for Booster Station		
Fuel	Usage	Cost
Electricity	73,201 kWh	\$11,419
Total		\$11,419

The current annual energy cost for this facility is \$11,419 as shown in the chart below.

*Figure 7 - Energy Cost Breakdown*



### 3.2 Electricity Usage

Electricity is provided by PSE&G. The average electric cost over the past 12 months was \$0.156/kWh, which is the blended rate that includes energy supply, distribution, and other charges. This rate is used throughout the analyses in this report to assess energy costs and savings. The facility has a peak demand of 58.2 kW and is billed demand charges. For the evaluation period there were only two months of non-utility estimated data, this data was extrapolated to the other months as the motor runtime is constant at 6 hours per day. The monthly electricity consumption and peak demand are shown in the chart below.

Figure 8 - Electric Usage & Demand




Figure 9 - Electric Usage & Demand

Electric Billing Data for Booster Station					
Period Ending	Days in Period	Electric Usage (kWh)	Demand (kW)	Demand Cost	Total Electric Cost
6/25/15	28	5,615	58	\$256	\$876
7/27/15	32	6,418	58	\$256	\$1,001
8/25/15	29	5,816	58	\$256	\$907
9/24/15	30	6,017	58	\$256	\$939
10/23/15	29	5,816	58	\$256	\$907
11/23/15	31	6,217	58	\$256	\$970
12/24/15	31	6,217	58	\$256	\$970
1/27/16	34	6,819	58	\$256	\$1,064
2/25/16	29	5,816	58	\$256	\$907
3/28/16	32	6,418	58	\$256	\$1,001
4/26/16	29	5,816	58	\$256	\$907
5/25/16	29	5,816	58	\$256	\$907
<b>Totals</b>	<b>363</b>	<b>72,800</b>	<b>58.2</b>	<b>\$3,076</b>	<b>\$11,357</b>
<b>Annual</b>	<b>365</b>	<b>73,201</b>	<b>58.2</b>	<b>\$3,093</b>	<b>\$11,419</b>

### 3.3 Benchmarking

This facility was benchmarked using Portfolio Manager, an online tool created and managed by the United States Environmental Protection Agency (EPA) through the ENERGY STAR® program. Portfolio Manager analyzes your building’s consumption data, cost information, and operational use details and then compares its performance against a national median for similar buildings of its type. Metrics provided by this analysis are Energy Use Intensity (EUI) and an ENERGY STAR® Score for select building types.

The EUI is a measure of a facility’s energy consumption per square foot, and it is the standard metric for comparing buildings’ energy performance. Comparing the EUI of a building with the national median EUI for that building type illustrates whether that building uses more or less energy than similar buildings of its type on a square foot basis. EUI is presented in terms of “site energy” and “source energy.” Site energy is the amount of fuel and electricity consumed by a building as reflected in utility bills. Source energy includes fuel consumed to generate electricity consumed at the site, factoring in electric production and distribution losses for the region.

**Figure 10 - Energy Use Intensity Comparison – Existing Conditions**

Energy Use Intensity Comparison - Existing Conditions		
	Booster Station	National Median Building Type: Water/Wastewater Treatment/Pumping
Source Energy Use Intensity (kBtu/ft <sup>2</sup> )	2178.5	123.1
Site Energy Use Intensity (kBtu/ft <sup>2</sup> )	693.8	78.8

Implementation of all recommended measures in this report would improve the building’s estimated EUI significantly, as shown in the table below:

**Figure 11 - Energy Use Intensity Comparison – Following Installation of Recommended Measures**

Energy Use Intensity Comparison - Following Installation of Recommended Measures		
	Booster Station	National Median Building Type: Water/Wastewater Treatment/Pumping
Source Energy Use Intensity (kBtu/ft <sup>2</sup> )	1899.9	123.1
Site Energy Use Intensity (kBtu/ft <sup>2</sup> )	605.1	78.8

Many types of commercial buildings are also eligible to receive an ENERGY STAR® score. This score is a percentile ranking from 1 to 100. It compares your building’s energy performance to similar buildings nationwide. A score of 50 represents median energy performance, while a score of 75 means your building performs better than 75 percent of all similar buildings nationwide and may be eligible for ENERGY STAR® certification. Your building is not one of the building categories that are eligible to receive a score.

A Portfolio Manager Statement of Energy Performance (SEP) was generated for this facility, see Appendix B: ENERGY STAR® Statement of Energy Performance.

For more information on ENERGY STAR® certification go to: <https://www.energystar.gov/buildings/facility-owners-and-managers/existing-buildings/earn-recognition/energy-star-certification/how-app-1>.


A Portfolio Manager account has been created online for your facility and you will be provided with the login information for the account. We encourage you to update your utility information in Portfolio Manager regularly, so that you can keep track of your building's performance. Free online training is available to help you use ENERGY STAR® Portfolio Manager to track your building's performance at: <https://www.energystar.gov/buildings/training>.



### 3.4 Energy End-Use Breakdown

In order to provide a complete overview of energy consumption across building systems, an energy balance was performed at this facility. An energy balance utilizes standard practice engineering methods to evaluate all components of the various electric and fuel-fired systems found in a building to determine their proportional contribution to overall building energy usage. This chart of energy end uses highlights the relative contribution of each equipment category to total energy usage. This can help determine where the greatest benefits might be found from energy efficiency measures.

Figure 12 - Energy Balance (% and kBtu/SF)



## 4 ENERGY CONSERVATION MEASURES

### Level of Analysis

The goal of this audit report is to identify potential energy efficiency opportunities, help prioritize specific measures for implementation, and provide information to the Booster Station regarding financial incentives for which they may qualify to implement the recommended measures. For this audit report, most measures have received only a preliminary analysis of feasibility which identifies expected ranges of savings and costs. This level of analysis is usually considered sufficient to demonstrate project cost-effectiveness and help prioritize energy measures. Savings are based on the New Jersey Clean Energy Program Protocols to Measure Resource Savings dated June 29, 2016, approved by the New Jersey Board of Public Utilities. Further analysis or investigation may be required to calculate more precise savings based on specific circumstances. A higher level of investigation may be necessary to support any custom SmartStart or Pay for Performance, or Direct Install incentive applications. Financial incentives for the ECMs identified in this report have been calculated based the NJCEP prescriptive SmartStart program. Some measures and proposed upgrade projects may be eligible for higher incentives than those shown below through other NJCEP programs as described in Section 8.

The following sections describe the evaluated measures.

### 4.1 Recommended ECMs

The measures below have been evaluated by the auditor and are recommended for implementation at the facility.

*Figure 13 – Summary of Recommended ECMs*

Energy Conservation Measure		Annual Electric Savings (kWh)	Peak Demand Savings (kW)	Annual Fuel Savings (MMBtu)	Annual Energy Cost Savings (\$)	Estimated Install Cost (\$)	Estimated Incentive (\$)*	Estimated Net Cost (\$)	Simple Payback Period (yrs)**	CO <sub>2</sub> e Emissions Reduction (lbs)
<b>Motor Upgrades</b>		<b>3,143</b>	<b>0.9</b>	<b>0.0</b>	<b>\$490.29</b>	<b>\$6,936.66</b>	<b>\$0.00</b>	<b>\$6,936.66</b>	<b>14.1</b>	<b>3,165</b>
ECM 1	Premium Efficiency Motors	3,143	0.9	0.0	\$490.29	\$6,936.66	\$0.00	\$6,936.66	14.1	3,165
<b>Electric Unitary HVAC Measures</b>		<b>6,220</b>	<b>0.0</b>	<b>0.0</b>	<b>\$970.25</b>	<b>\$7,197.54</b>	<b>\$276.00</b>	<b>\$6,921.54</b>	<b>7.1</b>	<b>6,263</b>
ECM 2	Install High Efficiency Heat Pumps	6,220	0.0	0.0	\$970.25	\$7,197.54	\$276.00	\$6,921.54	7.1	6,263
<b>TOTALS</b>		<b>9,362</b>	<b>0.9</b>	<b>0.0</b>	<b>\$1,460.54</b>	<b>\$14,134.20</b>	<b>\$276.00</b>	<b>\$13,858.20</b>	<b>9.5</b>	<b>9,428</b>

\* - All incentives presented in this table are based on NJ Smart Start Building equipment incentives and assume proposed equipment meets minimum performance criteria for that program.

\*\* - Simple Payback Period is based on net measure costs (i.e. after incentives).

## 4.1.1 Motor Upgrades

Our recommendations for motor upgrades are summarized in Figure 14 below.

**Figure 14 - Summary of Motor Upgrade ECMs**

Energy Conservation Measure	Annual Electric Savings (kWh)	Peak Demand Savings (kW)	Annual Natural Gas Savings (MMBtu)	Annual N/A Savings (MMBtu)	Annual N/A Savings (MMBtu)	Annual Fuel Savings (MMBtu)	Annual Energy Cost Savings (\$)	Estimated Install Cost (\$)	Estimated Incentive (\$)*	Estimated Net Cost (\$)	Simple Payback Period (yrs)**	CO <sub>2</sub> e Emissions Reduction (lbs)
<b>Motor Upgrades</b>	<b>3,143</b>	<b>0.9</b>	<b>0.0</b>	<b>0.0</b>	<b>0.0</b>	<b>0.0</b>	<b>\$490.29</b>	<b>\$6,936.66</b>	<b>\$0.00</b>	<b>\$6,936.66</b>	<b>14.1</b>	<b>3,165</b>
ECM 1   Premium Efficiency Motors	3,143	0.9	0.0	0.0	0.0	0.0	\$490.29	\$6,936.66	\$0.00	\$6,936.66	14.1	3,165

### **ECM 1: Premium Efficiency Motors**

#### *Summary of Measure Economics*

Annual Electric Savings (kWh)	Peak Demand Savings (kW)	Annual Fuel Savings (MMBtu)	Annual Energy Cost Savings (\$)	Estimated Install Cost (\$)	Estimated Incentive (\$)	Estimated Net Cost (\$)	Simple Payback Period (yrs)	CO <sub>2</sub> e Emissions Reduction (lbs)
3,143	0.9	0.0	\$490.29	\$6,936.66	\$0.00	\$6,936.66	14.1	3,165

#### *Measure Description*

We recommend replacing standard efficiency motors with NEMA Premium® efficiency motors. Our evaluation assumes that existing motors will be replaced with motors of equivalent size and type. Although occasionally additional savings can be achieved by downsizing motors to better meet the motor's current load requirements. The base case motor efficiencies are estimated from nameplate information and our best estimates of motor run hours. Efficiencies of proposed motor upgrades are obtained from the New Jersey's Clean Energy Program Protocols to Measure Resource Savings (2016). Savings are based on the difference between baseline and proposed efficiencies and the assumed annual operating hours.

## 4.1.2 Electric Unitary HVAC Measures

Our recommendations for unitary HVAC measures are summarized in Figure 15 below.

*Figure 15 - Summary of Unitary HVAC ECMs*

Energy Conservation Measure		Annual Electric Savings (kWh)	Peak Demand Savings (kW)	Annual Fuel Savings (MMBtu)	Annual Energy Cost Savings (\$)	Estimated Install Cost (\$)	Estimated Incentive (\$)	Estimated Net Cost (\$)	Simple Payback Period (yrs)	CO <sub>2</sub> e Emissions Reduction (lbs)
<b>Electric Unitary HVAC Measures</b>		<b>6,220</b>	<b>0.0</b>	<b>0.0</b>	<b>\$970.25</b>	<b>\$7,197.54</b>	<b>\$276.00</b>	<b>\$6,921.54</b>	<b>7.1</b>	<b>6,263</b>
ECM 2	Install High Efficiency Heat Pumps	6,220	0.0	0.0	\$970.25	\$7,197.54	\$276.00	\$6,921.54	7.1	6,263

### **ECM 2: Install High Efficiency Heat Pumps**

#### *Summary of Measure Economics*

Annual Electric Savings (kWh)	Peak Demand Savings (kW)	Annual Fuel Savings (MMBtu)	Annual Energy Cost Savings (\$)	Estimated Install Cost (\$)	Estimated Incentive (\$)	Estimated Net Cost (\$)	Simple Payback Period (yrs)	CO <sub>2</sub> e Emissions Reduction (lbs)
6,220	0.0	0.0	\$970.25	\$7,197.54	\$276.00	\$6,921.54	7.1	6,263

#### *Measure Description*

We recommend replacing standard electric resistance heat with high efficiency heat pumps. There have been significant improvements in both compressor and fan motor efficiencies over the past several years. Therefore, electricity savings can be achieved by replacing older units with new high efficiency units. A higher EER or SEER rating indicates a more efficient cooling system and a higher HPSF rating indicates more efficient heating mode. The magnitude of energy savings for this measure depends on the relative efficiency of the older unit versus the new high efficiency unit, the average heating and cooling loads, and the estimated annual operating hours.

## 5 ENERGY EFFICIENT PRACTICES

---

In addition to the quantifiable savings estimated in Section 4, a facility's energy performance can also be improved through application of many low cost or no-cost energy efficiency strategies. By employing certain behavioral and operational changes and performing routine maintenance on building systems, equipment lifetime can be extended; occupant comfort, health and safety can be improved; and energy and O&M costs can be reduced. The recommendations below are provided as a framework for developing a whole building maintenance plan that is customized to your facility. Consult with qualified equipment specialists for details on proper maintenance and system operation.

### **Reduce Air Leakage**

Air leakage, or infiltration, occurs when outside air enters a building uncontrollably through cracks and openings. Properly sealing such cracks and openings can significantly reduce heating and cooling costs, improve building durability, and create a healthier indoor environment. This includes caulking or installing weather stripping around leaky doors and windows allowing for better control of indoor air quality through controlled ventilation.

### **Close Doors and Windows**

Ensure doors and windows are closed in conditioned spaces. Leaving doors and windows open leads to a significant increase in heat transfer between conditioned spaces and the outside air. Reducing a facility's air changes per hour (ACH) can lead to increased occupant comfort as well as significant heating and cooling savings, especially when combined with proper HVAC controls and adequate ventilation.

### **Develop a Lighting Maintenance Schedule**

In addition to routine fixture cleaning, development of a maintenance schedule can both ensure maintenance is performed regularly and can reduce the overall cost of fixture re-lamping and re-ballasting. By re-lamping and re-ballasting fixtures in groups, lighting levels are better maintained and the number of site visits by a lighting technician or contractor can be minimized, decreasing the overall cost of maintenance.

## 6 ON-SITE GENERATION MEASURES

---

On-site generation measure options include both renewable (e.g., solar, wind) and non-renewable (e.g., fuel cells) on-site technologies that generate power to meet all or a portion of the electric energy needs of a facility, often repurposing any waste heat where applicable. Also referred to as distributed generation, these systems contribute to Greenhouse Gas (GHG) emission reductions, demand reductions and reduced customer electricity purchases, resulting in the electric system reliability through improved transmission and distribution system utilization.

The State of New Jersey's Energy Master Plan (EMP) encourages new distributed generation of all forms and specifically focuses on expanding use of combined heat and power (CHP) by reducing financial, regulatory and technical barriers and identifying opportunities for new entries. The EMP also outlines a goal of 70% of the State's electrical needs to be met by renewable sources by 2050.

Preliminary screenings were performed to determine the potential that a generation project could provide a cost-effective solution for your facility. Before making a decision to implement, a feasibility study should be conducted that would take a detailed look at existing energy profiles, siting, interconnection, and the costs associated with the generation project including interconnection costs, departing load charges, and any additional special facilities charges.

### 6.1 Photovoltaic


Sunlight can be converted into electricity using photovoltaics (PV) modules. Modules are racked together into an array that produces direct current (DC) electricity. The DC current is converted to alternating current (AC) through an inverter. The inverter is interconnected to the facility's electrical distribution system. The amount of unobstructed area available determines how large of a solar array can be installed. The size of the array combined with the orientation, tilt, and shading elements determines the energy produced.

A preliminary screening based on the facility's electric demand, size and location of free area, and shading elements shows that the facility has a Low potential for installing a PV array.

The amount of free area, ease of installation (location), and the lack of shading elements contribute to the potential for PV at the site. A PV array located on the roof of the main building/ground next to the building/over the main parking lot may be feasible. If Booster Station is interested in pursuing the installation of PV, we recommended a full feasibility study be conducted.

In order to be cost-effective, a solar PV array needs certain minimum criteria, such as flat or south-facing rooftop or other unshaded space on which to place the PV panels. In our opinion, the facility does appear not meet these minimum criteria for cost-effective PV installation due to the lack of space high shading of the area.

**Figure 16 - Photovoltaic Screening**



For more information on solar PV technology and commercial solar markets in New Jersey, or to find a qualified solar installer, who can provide a more detailed assessment of the specific costs and benefits of solar develop of the site, please visit the following links below:

- **Basic Info on Solar PV in NJ:** <http://www.njcleanenergy.com/whysolar>
- **NJ Solar Market FAQs:** <http://www.njcleanenergy.com/renewable-energy/program-updates-and-background-information/solar-transition/solar-market-faqs>
- **Approved Solar Installers in the NJ Market:** [http://www.njcleanenergy.com/commercial-industrial/programs/nj-smartstart-buildings/tools-and-resources/tradeally/approved\\_vendorsearch/?id=60&start=1](http://www.njcleanenergy.com/commercial-industrial/programs/nj-smartstart-buildings/tools-and-resources/tradeally/approved_vendorsearch/?id=60&start=1)

## 6.2 Combined Heat and Power

Combined heat and power (CHP) is the on-site generation of electricity along with the recovery of heat energy, which is put to beneficial use. Common technologies for CHP include reciprocating engines, microturbines, fuel cells, backpressure steam turbines, and (at large facilities) gas turbines. Electric generation from a CHP system is typically interconnected to local power distribution systems. Heat is recovered from exhaust and ancillary cooling systems and interconnected to the existing hot water (or steam) distribution systems.


CHP systems are typically used to produce a portion of the electric power used onsite by a facility, with the balance of electric power needs supplied by grid purchases. The heat is used to supplement (or supplant) existing boilers for the purpose of space heating and/or domestic hot water heating. Waste heat can also be routed through absorption chillers for the purpose of space cooling. The key criteria used for screening, however, is the amount of time the system operates at full load and the facility's ability to use the recovered heat. Facilities with continuous use for large quantities of waste heat are the best candidates for CHP.

A preliminary screening based on heating and electrical demand, siting, and interconnection shows that the facility has a Low potential for installing a cost-effective CHP system.

In our opinion, the facility does not appear to meet the minimum requirements for a cost-effective CHP installation due to the low thermal load for the facility.

For a list of qualified firms in New Jersey specializing in commercial CHP cost assessment and installation, go to: [http://www.njcleanenergy.com/commercial-industrial/programs/nj-smartstart-buildings/tools-and-resources/tradeally/approved\\_vendorsearch/](http://www.njcleanenergy.com/commercial-industrial/programs/nj-smartstart-buildings/tools-and-resources/tradeally/approved_vendorsearch/).

**Figure 17 - Combined Heat and Power Screening**





## 7 DEMAND RESPONSE

---

Demand Response (DR) is a program designed to reduce the electric load of commercial facilities when electric wholesale prices are high or when the reliability of the electric grid is threatened due to peak demand. Demand Response service providers (a.k.a. Curtailment Service Providers) are registered with PJM, the independent system operator (ISO) for mid-Atlantic state region that is charged with maintaining electric grid reliability.

By enabling grid operators to call upon Curtailment Service Providers and commercial facilities to reduce electric usage during times of peak demand, the grid is made more reliable and overall transmission costs are reduced for all ratepayers. Curtailment Service Providers provide regular payments to medium and large consumers of electric power for their participation in DR programs. Program participation is voluntary and participants receive payments whether or not their facility is called upon to curtail their electric usage.

Typically, an electric customer needs to be capable of reducing their electric demand, within minutes, by at least 100 kW or more in order to participate in a DR program. Customers with a greater capability to quickly curtail their demand during peak hours will receive higher payments. Customers with back-up generators onsite may also receive additional DR payments for their generating capacity if they agree to run the generators for grid support when called upon. Eligible customers who have chosen to participate in a DR programs often find it to be a valuable source of revenue for their facility because the payments can significantly offset annual electric costs.

Participating customers can often quickly reduce their peak load through simple measures, such as temporarily raising temperature set points on thermostats, so that air conditioning units run less frequently, or agreeing to dim or shut off less critical lighting. This usually requires some level of building automation and controls capability to ensure rapid load reduction during a DR curtailment event. DR program participants may need to install smart meters or may need to also sub-meter larger energy-using equipment, such as chillers, in order to demonstrate compliance with DR program requirements.

DR does not include the reduction of electricity consumption based on normal operating practice or behavior. For example, if a company's normal schedule is to close for a holiday, the reduction of electricity due to this closure or scaled-back operation is not considered a demand response activity in most situations.

The first step toward participation in a DR program is to contact a Curtailment Service Provider. A list of these providers is available on PJM's website and it includes contact information for each company, as well as the states where they have active business (<http://www.pjm.com/markets-and-operations/demand-response/csps.aspx>). PJM also posts training materials that are developed for program members interested in specific rules and requirements regarding DR activity (<http://www.pjm.com/training/training%20material.aspx>), along with a variety of other DR program information.

Curtailment Service Providers typically offer free assessments to determine a facility's eligibility to participate in a DR program. They will provide details regarding program rules and requirements for metering and controls, assess a facility's ability to temporarily reduce electric load, and provide details on payments to be expected for participation in the program. Providers usually offer multiple options for DR to larger facilities and may also install controls or remote monitoring equipment of their own to help ensure compliance with all terms and conditions of a DR contract.

## 8 PROJECT FUNDING / INCENTIVES

The NJCEP is able to provide the incentive programs described below, and other benefits to ratepayers, because of the Societal Benefits Charge (SBC) Fund. The SBC was created by the State of New Jersey’s Electricity Restructuring Law (1999), which requires all customers of investor-owned electric and gas utilities to pay a surcharge on their monthly energy bills. As a customer of a state-regulated electric or gas utility and therefore a contributor to the fund your organization is eligible to participate in the LGEA program and also eligible to receive incentive payment for qualifying energy efficiency measures. Also available through the NJBPU are some alternative financing programs described later in this section. Please refer to Figure 18 for a list of the eligible programs identified for each recommended ECM.

*Figure 18 - ECM Incentive Program Eligibility*

Energy Conservation Measure		SmartStart Prescriptive	SmartStart Custom	Direct Install	Pay For Performance Existing Buildings	Large Energy Users Program	Combined Heat & Power and Fuel Cell
ECM 1	Premium Efficiency Motors	x		x			
ECM 2	Install High Efficiency Heat Pumps	x		x			

SmartStart is generally well-suited for implementation of individual measures or small group of measures. It provides flexibility to install measures at your own pace using in-house staff or a preferred contractor. Direct Install caters to small to mid-size facilities that can bundle multiple ECMs together. This can greatly simplify participation and may lead to higher incentive amounts, but requires the use of pre-approved contractors.

Generally, the incentive values provided throughout the report assume the SmartStart program is utilized because it provides a consistent basis for comparison of available incentives for various measures, though in many cases incentive amounts may be higher through participation in other programs.

Brief descriptions of all relevant financing and incentive programs are located in the sections below. Further information, including most current program availability, requirements, and incentive levels can be found at: [www.njcleanenergy.com/ci](http://www.njcleanenergy.com/ci).

## 8.1 SmartStart

### Overview

The SmartStart program offers incentives for installing prescriptive and custom energy efficiency measures at your facility. Routinely the program adds, removes or modifies incentives from year to year for various energy efficiency equipment based on market trends and new technologies.

### **Equipment with Prescriptive Incentives Currently Available:**

*Electric Chillers*

*Electric Unitary HVAC*

*Gas Cooling*

*Gas Heating*

*Gas Water Heating*

*Ground Source Heat Pumps*

*Lighting*

*Lighting Controls*

*Refrigeration Doors*

*Refrigeration Controls*

*Refrigerator/Freezer Motors*

*Food Service Equipment*

*Variable Frequency Drives*

Most equipment sizes and types are served by this program. This program provides an effective mechanism for securing incentives for energy efficiency measures installed individually or as part of a package of energy upgrades.

### Incentives

The SmartStart prescriptive incentive program provides fixed incentives for specific energy efficiency measures, whereas the custom SmartStart program provides incentives for more unique or specialized technologies or systems that are not addressed through prescriptive incentive offerings for specific devices.

Since your facility is an existing building, only the retrofit incentives have been applied in this report. Custom Measure incentives are calculated at \$0.16/kWh and \$1.60/therm based on estimated annual savings, capped at 50% of the total installed incremental project cost, or a project cost buy down to a one-year payback (whichever is less). Program incentives are capped at \$500,000 per electric account and \$500,000 per natural gas account, per fiscal year.

### How to Participate

To participate in the SmartStart program you will need to submit an application for the specific equipment to be installed. Many applications are designed as rebates, although others require application approval prior to installation. Applicants may work with a contractor of their choosing and can also utilize internal personnel, which provides added flexibility to the program. Using internal personnel also helps improve the economics of the ECM by reducing the labor cost that is included in the tables in this report.

Detailed program descriptions, instructions for applying and applications can be found at: [www.njcleanenergy.com/SSB](http://www.njcleanenergy.com/SSB).

## 8.2 Direct Install

### Overview

Direct Install is a turnkey program available to existing small to medium-sized facilities with a peak electric demand that does not exceed 200 kW for any recent 12-month period. You will work directly with a pre-approved contractor who will perform a free energy assessment at your facility, identify specific eligible measures, and provide a clear scope of work for installation of selected measures. Energy efficiency measures may include lighting and lighting controls, refrigeration, HVAC, motors, variable speed drives and controls.

### Incentives

The program pays up to 70% of the total installed cost of eligible measures, up to \$125,000 per project. Direct Install participants will also be held to a fiscal year cap of \$250,000 per entity.

### How to Participate

To participate in the Direct Install program, you will need to contact the participating contractor who the region of the state where your facility is located. A complete list of Direct Install program partners is provided on the Direct Install website linked below. The contractor will be paid the measure incentives directly by the program which will pass on to you in the form of reduced material and implementation costs. This means up to 70% of eligible costs are covered by the program, subject to program caps and eligibility, while the remaining 30% of the cost is paid to the contractor by the customer.

Since Direct Install offers a free assessment of eligible measures, Direct Install is also available to small businesses and other commercial facilities too that may not be eligible for the more detailed facility audits provided by LGEA.

Detailed program descriptions and applications can be found at: [www.njcleanenergy.com/DI](http://www.njcleanenergy.com/DI).

## 9 ENERGY PURCHASING AND PROCUREMENT STRATEGIES

---

### 9.1 Retail Electric Supply Options

In 1999, New Jersey State Legislature passed the Electric Discount & Energy Competition Act (EDECA) to restructure the electric power industry in New Jersey. This law deregulated the retail electric markets, allowing all consumers to shop for service from competitive electric suppliers. The intent was to create a more competitive market for electric power supply in New Jersey. As a result, utilities were allowed to charge Cost of Service and customers were given the ability to choose a third party (i.e. non-utility) energy supplier.

Energy deregulation in New Jersey has increased energy buyers' options by separating the function of electricity distribution from that of electricity supply. So, though you may choose a different company from which to buy your electric power, responsibility for your facility's interconnection to the grid and repair to local power distribution will still reside with the traditional utility company serving your region.

If your facility is not purchasing electricity from a third party supplier, consider shopping for a reduced rate from third party electric suppliers. If your facility is purchasing electricity from a third party supplier, review and compare prices at the end of the current contract or every couple years.

A list of third party electric suppliers, who are licensed by the state to provide service in New Jersey, can be found online at: [www.state.nj.us/bpu/commercial/shopping.html](http://www.state.nj.us/bpu/commercial/shopping.html).

### 9.2 Retail Natural Gas Supply Options

The natural gas market in New Jersey has also been deregulated. Most customers that remain with the utility for natural gas service pay rates that are market-based and that fluctuate on a monthly basis. The utility provides basic gas supply service (BGSS) to customers who choose not to buy from a third party supplier for natural gas commodity.

A customer's decision about whether to buy natural gas from a retail supplier is typically dependent upon whether a customer seeks budget certainty and/or longer-term rate stability. Customers can secure longer-term fixed prices by signing up for service through a third party retail natural gas supplier. Many larger natural gas customers may seek the assistance of a professional consultant to assist in their procurement process.

If your facility is not purchasing natural gas from a third party supplier, consider shopping for a reduced rate from third party natural gas suppliers. If your facility is purchasing natural gas from a third party supplier, review and compare prices at the end of the current contract or every couple years.

A list of third party natural gas suppliers, who are licensed by the state to provide service in New Jersey, can be found online at: [www.state.nj.us/bpu/commercial/shopping.html](http://www.state.nj.us/bpu/commercial/shopping.html).

# Appendix A: Equipment Inventory & Recommendations

## Lighting Inventory & Recommendations

Location	Existing Conditions					Proposed Conditions							Energy Impact & Financial Analysis						
	Fixture Quantity	Fixture Description	Control System	Watts per Fixture	Annual Operating Hours	Fixture Recommendation	Add Controls?	Fixture Quantity	Fixture Description	Control System	Watts per Fixture	Annual Operating Hours	Total Peak kW Savings	Total Annual kWh Savings	Total Annual MMBtu Savings	Total Annual Energy Cost Savings	Total Installation Cost	Total Incentives	Simple Payback w/ Incentives in Years
Interior	2	Linear Fluorescent - T8: 8' T8 (59W) - 2L	None	110	650	None	No	2	Linear Fluorescent - T8: 8' T8 (59W) - 2L	None	110	650	0.00	0	0.0	\$0.00	\$0.00	\$0.00	0.00
Exterior	1	LED - Fixtures: Outdoor Wall-Mounted Area Fixture	None	30	4,500	None	No	1	LED - Fixtures: Outdoor Wall-Mounted Area Fixture	None	30	4,500	0.00	0	0.0	\$0.00	\$0.00	\$0.00	0.00
Exterior	1	LED - Fixtures: Outdoor Wall-Mounted Area Fixture	None	20	4,500	None	No	1	LED - Fixtures: Outdoor Wall-Mounted Area Fixture	None	20	4,500	0.00	0	0.0	\$0.00	\$0.00	\$0.00	0.00


## Motor Inventory & Recommendations

Location	Area(s)/System(s) Served	Existing Conditions						Proposed Conditions				Energy Impact & Financial Analysis						
		Motor Quantity	Motor Application	HP Per Motor	Full Load Efficiency	VFD Control?	Annual Operating Hours	Install High Efficiency Motors?	Full Load Efficiency	Install VFDs?	Number of VFDs	Total Peak kW Savings	Total Annual kWh Savings	Total Annual MMBtu Savings	Total Annual Energy Cost Savings	Total Installation Cost	Total Incentives	Simple Payback w/ Incentives in Years
Interior	Town	2	Process Pump	25.0	89.9%	No	2,555	Yes	93.6%	No		0.91	3,143	0.0	\$490.29	\$6,936.66	\$0.00	14.15

## Electric HVAC Inventory & Recommendations

Location	Area(s)/System(s) Served	Existing Conditions					Proposed Conditions						Energy Impact & Financial Analysis							
		System Quantity	System Type	Cooling Capacity per Unit (Tons)	Heating Capacity per Unit (kBtu/hr)	Install High Efficiency System?	System Quantity	System Type	Cooling Capacity per Unit (Tons)	Heating Capacity per Unit (kBtu/hr)	Cooling Mode Efficiency (SEER/EER)	Heating Mode Efficiency (COP)	Install Dual Enthalpy Economizer?	Total Peak kW Savings	Total Annual kWh Savings	Total Annual MMBtu Savings	Total Annual Energy Cost Savings	Total Installation Cost	Total Incentives	Simple Payback w/ Incentives in Years
Building	Building	1	Electric Resistance Heat		36.00	Yes	1	Ductless Mini-Split HP	3.00	60.00	18.00	3.80	No	0.00	6,220	0.0	\$970.25	\$7,197.54	\$276.00	7.13

## Appendix B: ENERGY STAR® Statement of Energy Performance


ENERGY STAR® Statement of Energy Performance

N/A

**Booster Station**

Primary Property Type: Drinking Water Treatment & Distribution  
 Gross Floor Area (ft<sup>2</sup>): 360  
 Built: 1999

For Year Ending: April 30, 2016  
 Date Generated: October 18, 2017

**ENERGY STAR® Score<sup>1</sup>**

1. The ENERGY STAR score is a 1-100 assessment of a building's energy efficiency as compared with similar buildings nationwide, adjusting for climate and business activity.

Property & Contact Information		
Property Address	Property Owner	Primary Contact
Booster Station 55 North Hillside Avenue Livingston, New Jersey 07039	_____	_____
Property ID: 6077414	( ) . _____	( ) . _____

Energy Consumption and Energy Use Intensity (EUI)			
<b>Site EUI</b>	Annual Energy by Fuel	National Median Comparison	
694 kBtu/ft <sup>2</sup>	Electric - Grid (kBtu) 249,832 (100%)	National Median Site EUI ( )	N/A
		National Median Source EUI ( )	N/A
		% Diff from National Median Source EUI	N/A%
<b>Source EUI</b>		Annual Emissions	
2,179.1 kBtu/ft <sup>2</sup>		Greenhouse Gas Emissions (Metric Tons CO <sub>2</sub> e/year)	28

### Signature & Stamp of Verifying Professional

I \_\_\_\_\_ (Name) verify that the above information is true and correct to the best of my knowledge.

Signature: \_\_\_\_\_ Date: \_\_\_\_\_

Licensed Professional

\_\_\_\_\_  
 ( ) . \_\_\_\_\_  
 \_\_\_\_\_



Professional Engineer Stamp  
(if applicable)