

Pay for Performance - NC Technical Topic

Commissioning Resources and Clarifications

Executive Summary

This Technical Topic provides resources and clarifications for commissioning requirements of the Pay for Performance New Construction Program, and is intended to be a supplemental reference to Section 6 of the Program Guidelines.

Commissioning (Cx) is an ongoing collaborative and quality process between the owner, design team, contractors, and the Cx Authority (CxA) to confirm that owner's project requirements are being met. The process focuses on verifying and documenting the facility and its systems are designed, installed, tested, operated and maintained to meet these requirements, and as a result, is expected to take place from pre-design and design stages through construction completion and post-construction/occupancy.

Commissioning, including preparation of the Commissioning Plan, is a mandatory requirement of the P4P New Construction Program. Projects that are not commissioned are not eligible for any P4P NC incentives.

The tables and examples provided in the technical topic are intended to demonstrate the level of detail required for Cx plans and reports with the understanding that every project is unique. Although a Cx Plan Template is provided by the program, there is no specific format for commissioning reports and it's expected that CxA's will use their own templates. Topics included in this technical topic are highlighted in bold below.

Post-Construction Pre-design Stage **Design Stage Construction Stage** Occupancy & Operations: Project Initiation / Kick-off • Update / Expand Pre-design Update / Expand Design Update Construction Stage Stage Documents Stage Documents Documents Owner and CxA develop Owner's Project Design Team Develops System Cooridination Plans • Maintenance Program Requirements (OPR) Basis of Design (BOD) Pre-Functional and • Final Issues and Resolution Cx Plan Draft CxA confirms BOD meets Functional Performance • Systems Manual Outline Final Issues Report Construction Specifications Develop Test Procedures Training Requirements Final Commissioning Report for Cx Outline Testing and Balancing • Re-Commissioning Plan CxA Design Document Formats for Cx Report and Reports Review Comments • Cx Meetings, Agendas, and Issues & Resolutions Log CxA Submittal Documents Minutes **Review Comments** Training Plans Issues and Resolution Log Systems Manual • Design Cx Process Report Issues and Resolution Log • Finalize Cx Plan Final Construction Cx Report

Figure 1 Commissioning Milestones and Sub-milestones

Commissioning Standards and Guidelines



The Commissioning Process


ASHRAE Guideline 0 - The Commission Process – This Guideline describes the Commissioning Process capable of verifying that a facility and its systems meet the Owner's Project Requirements. The procedures, methods, and documentation requirements in this guideline describe each phase of the project delivery and the associated Commissioning Processes from pre-design through occupancy and operation.

Aground to the ASPARE Storbeth Convention on Relative 3, 2006, on the the ASPARE, Board of Thomson on Rech 11, 2006.
This guidables an under constituent an estimator in the Storbeth Convention (SPCC) for which the Storbeth Convention (SPCC) are shown that the Storbeth Convention (SPCC) are shown that the Storbeth Convention Convention (SPCC) are shown that the Storbeth Convention (SPCC) are shown that the Storbeth Convention (SPCC) are shown to U.S. and Storbeth Convention (SPCC) are shown to U.S. and Storbeth Convention (SPCC) are shown to U.S. and Convention (SPCC) are show

The guideline also contains numerous appendices that contain examples how to execute Cx activities as well as sample forms (e.g. construction / testing checklists).

ASHRAE Standard 202p - The Commission Process - This Standard describes how to plan, conduct, and document commissioning activities. Informative appendices provide sample documentation, including checklists, systems manual, reports, training plan, among other resources.

ASHRAE has two additional commissioning guidelines, Guideline 1.1 and Guideline 1.5. Guideline 1.1-2007 focuses on HVAC&R systems while addressing total building commissioning processes by validating interfaces and possible interferences between all building systems. Guideline 1.5 describes the technical requirements for the application of the Commissioning Process described in ASHRAE Guideline 0 that will verify that the smoke control system achieves the Owner's Project Requirements (OPR).



All ASHRAE Commissioning Guidelines are available at the ASHRAE bookstore in both electronic forms and print editions:

https://www.ashrae.org/resources--publications/bookstore/commissioning-essentials

Owner's Project Requirements (OPR)

Definition¹– A document that details the functional requirements of a project and the expectations of how it will be used and operated. These include project goals, measurable performance criteria, cost considerations, benchmarks, success criteria, and supporting information. (The term Project Intent is used by some owners for their Commissioning Process Owner's Project Requirements).

Section 5.2.2.4 of ASHRAE Guideline 0 contains a comprehensive list of items that should be included in the OPR. Informative Annex I contains an example how to collect information for the OPR and Informative Annex J contains a sample format to compile this information into an OPR document.

The Owner's Project Requirements are generally a collaborative effort between the Owner and Commissioning Authority (CxA). During the predesign phase, the Owner's Project Requirements (OPR) should be established to understand the owner's needs and goals. Information about the project is gathered, including program requirements, community context, codes and regulations, site and climate, facility context and function, facility technology, sustainability, cost, schedule, and the client's (including owner, occupants, operators, and maintenance personnel) needs and capabilities². The OPR is the basis of the commissioning plan, and informs the project team to properly design, construct, and operate a building and its systems.

"The OPR document must clearly reflect the priorities and objectives of the building owner. That's why a successful project team must include a skilled CxA who can work closely with the owner to help capture the details of the owner's requirements."

Dave McFarlane, "Technical vs. Process Commissioning Owner's Project Requirements," ASHRAE Journal, August 2013

Program Requirements

For the FY2017 program, per Section 3.2 of the Program Guidelines, to earn pre-design incentives, Partners must document how preliminary "simple box" energy modeling analysis informed building design decisions relative to owner's project requirements, basis of design, and eventual design of the project.

Inclusion of the Owner's Project Requirements (OPR) document in the Commissioning Plan (or as an Appendix to the Commissioning Plan) is required to demonstrate pre-design activities took place and earn pre-design bonus incentives.

¹ ASHRAE Guideline 0-2013 Section 4

² ASHRAE Guideline 0-2013 Section 5.1.1

Basis of Design (BOD) Document

Definition³— A document that records the concepts, calculations, decisions, and product selections used to meet the Owner's Project Requirements and to satisfy applicable regulatory requirements, standards, and guidelines. The document includes both narrative descriptions and lists of individual items that support the design process. The Basis of Design is developed by the design team and is reviewed by the CxA.

The basis of design (BOD) document provides the design team with a tool to clearly present the assumptions and

"The BOD transforms the raw data from the owner's project requirements (OPR) document (the "what") into a detailed, technical, actionable plan (the "how") that will meet the owner's objectives—which will also help avoid the "scope creep" that can derail the project schedule and lead to budget overruns."

Vince Briones and Dave McFarlane, "Technical vs. Process Commissioning Basis of Design," ASHRAE Journal, October 2013

specifications used to develop construction documents to all parties involved from the owner through contractors and suppliers. The OPR can be considered as the foundation of the BOD. The BOD specifically addresses how each of the owner's project requirements are included in the building design. The BOD should generally include the following⁴:

System and assembly options

System and assembly selection reasoning

Facility, system, and assembly performance assumptions

- Assumptions for calculations/sizing
- · Analytical procedures and tools
- Environmental conditions
- Limiting conditions
- Reference make and model
- Operational assumptions

Narrative system and assembly descriptions

Codes, standards, guidelines, regulations, and other references

Owner guidelines and directives

Specific descriptions of systems and assemblies

Consultant, engineering, and architectural guidelines for design developed by the design team or others

Program Requirements

For both legacy projects (pre-FY2017 projects) and FY2017 projects, the Basis of Design (BOD) must be included in Section 4 of the Program's Commissioning Plan template.

³ ASHRAE Guideline 0-2013 Section 4

⁴ ASHRAE Guideline 0-2013 Section 6.2.2.1

Commissioning Scope for P4P – What About Systems and Components that are not Explicit P4P Measures?

While commissioning must cover all P4P measures, commissioning must also be performed on building components and systems that have a significant impact on projected energy savings of the building and operational needs of the owner, developer, and occupants. Excluding major systems from commissioning activities could have a significant impact on building operation post-construction and occupant comfort.

For example, a new construction multifamily building has a rooftop unit providing corridor OA that meets the Minimum Performance "Cx is intended to confirm that building equipment and systems meet the design intent and operational needs of the owner, developer, and occupants. Cx shall also confirm that the system performance assumptions documented in the Proposed ERP, ensuring the facility achieves the projected energy savings."

Program Guidelines Section 6.1

Standards and a new boiler that only meets ASHRAE 90.1 requirements. The scope of work includes wall and roof insulation, triple pane windows, and RTU measures, but the boiler is not included as a measure. The boiler must be commissioned because it impacts occupant comfort and has direct impact on the envelope measures.

For FY2017 projects, excluding major systems can significantly impact Incentive 3, which provides incentives for buildings that earn the ENERGY STAR Certification or ASHRAE Building Energy Quotient In-Operation Certification.

Commissioning Sampling – Construction Phase Testing and Verification

The level of commissioning rigor will often be dictated by project size and complexity. For P4P NC, the sampling strategy used must demonstrate confidence in the energy savings presented in the ERP in addition to meeting owner, developer, and occupant needs. The Program will not require specific sampling rates as each project has unique functional requirements. However, the program requires that *quality based* sampling is performed as discussed in the following excerpt from Guideline 0⁵.

"Because the contractor is responsible for 100% construction and checking of work, the commissioning process utilizes a sampling strategy in accomplishing verifications and tests. For construction checklist verifications, during site visits, the completed construction checklists are verified (typically 2%–10%). The following is general guidance for selecting and verifying construction checklists.

- 1. Identify the construction checklists that have been completed since the last site visit.
- 2. The following is a general guide for sample rates based on the number of new construction checklists. Please note that this is not meant to be used directly for your project due to the many variables in determining acceptable sample rates and owner input. Randomly select the construction checklists to be verified. Note that you often want to sample similar components as a group so that if there is only 1 or 2 of a particular component, it is not missed. Because the sampling rate is lower for these than for other components, you can compare results between similar components more easily."

| # New Construction Checklists | Overall Sample Rate | Component Sample Rate |
|-------------------------------|---------------------|-----------------------|
| 1–10 | 100% | 70%-100% |
| 11–20 | 80% | 50%-70% |
| 21–50 | 50% | 30%-50% |
| 51–100 | 30% | 15%-30% |
| >100 | 2–20% | 2%-10% |

Figure 2 Recommend Sampling Requirements from ASHRAE Guideline 0, Informative Appendix N

Program Requirements

With respect to the equipment/component testing activities of commissioning, sampling of systems is permitted if it generally follows the approach described above. The sampling procedure used should be described in the final commissioning report. Note that this approach is a rule of thumb and will not apply for all projects and scenarios. For example, for some building types, the criticality of systems must be considered (e.g. the sampling rate of 11 CRAH units in a data center should be higher than 70%).

_

⁵ Informative Annex N, Quality Based Sampling Examples of ASHRAE Guideline 0-2013

Schedules

The Commissioning Plan must include a schedule of Cx process activities. Generally, construction and commissioning schedules will be much more detailed and include several sub-milestones as well as duration. For the purposes of developing a Cx plan for P4P, a schedule with the level of detail similar to the one below may be used. The schedule must demonstrate that all Cx process activities have been integrated into design and construction.

| # Tasks Date Date 1 Complete Draft of OPR 2 Start Schematic Design 3 Commissioning Kick-off Meeting (Design) 4 Develop Draft of Commissioning Plan 5 CxA Schematic Design Review 5 Complete Schematic Design 6 Develop Draft of BOD 7 CxA Design Development Review 7 Complete Design Development 8 Complete Construction Documents 9 Pre-bid Meeting 10 Finalize Construction Contracts 11 Pre-construction Meeting 12 Review and Approve All Submittals 13 Commissioning Kick-off Meeting (Construction) 14 Construction Inspections 15 Complete Construction / Pre-Functional Testing Checklists 16 Complete Functional Performance Testing 17 Complete O&M and Systems Manual 18 Complete Training Manual 18 Conduct Maintenance Staff Training 19 Project Completion 20 Address All Outstanding Issues and Discrepancies 21 Warranty Review 22 Lessons Learned Meeting | | | Planned | Actual | | | |
|--|----|---|---------|--------|--|--|--|
| 2 Start Schematic Design 3 Commissioning Kick-off Meeting (Design) 4 Develop Draft of Commissioning Plan 5 CxA Schematic Design Review 5 Complete Schematic Design 6 Develop Draft of BOD 7 CxA Design Development Review 7 Complete Design Development 8 Complete Construction Documents 9 Pre-bid Meeting 10 Finalize Construction Contracts 11 Pre-construction Meeting 11 Start Construction 12 Review and Approve All Submittals 13 Commissioning Kick-off Meeting (Construction) 14 Construction Inspections 15 Complete Construction / Pre-Functional Testing Checklists 16 Complete Functional Performance Testing 17 Complete O&M and Systems Manual 18 Complete Training Manual 18 Conduct Maintenance Staff Training 19 Project Completion 20 Address All Outstanding Issues and Discrepancies 20 Finalize Commissioning Report 21 Warranty Review | | | Date | Date | | | |
| Commissioning Kick-off Meeting (Design) Develop Draft of Commissioning Plan CxA Schematic Design Review Complete Schematic Design Develop Draft of BOD CxA Design Development Review Complete Design Development Complete Construction Documents Pre-bid Meeting Finalize Construction Meeting Start Construction Meeting Review and Approve All Submittals Commissioning Kick-off Meeting (Construction) Construction Inspections Complete Construction / Pre-Functional Testing Checklists Complete Functional Performance Testing Complete O&M and Systems Manual Conduct Maintenance Staff Training Project Completion Address All Outstanding Issues and Discrepancies Finalize Commissioning Report Warranty Review | 1 | · | | | | | |
| 4 Develop Draft of Commissioning Plan 5 CxA Schematic Design Review 5 Complete Schematic Design 6 Develop Draft of BOD 7 CxA Design Development Review 7 Complete Design Development 8 Complete Construction Documents 9 Pre-bid Meeting 10 Finalize Construction Contracts 11 Pre-construction Meeting 11 Start Construction 12 Review and Approve All Submittals 13 Commissioning Kick-off Meeting (Construction) 14 Construction Inspections 15 Complete Construction / Pre-Functional Testing Checklists 16 Complete Functional Performance Testing 17 Complete O&M and Systems Manual 18 Conduct Maintenance Staff Training 19 Project Completion 20 Address All Outstanding Issues and Discrepancies 20 Finalize Commissioning Report 21 Warranty Review | 2 | _ | | | | | |
| 5 CxA Schematic Design Review 5 Complete Schematic Design 6 Develop Draft of BOD 7 CxA Design Development Review 7 Complete Design Development 8 Complete Construction Documents 9 Pre-bid Meeting 10 Finalize Construction Contracts 11 Pre-construction Meeting 11 Start Construction 12 Review and Approve All Submittals 13 Commissioning Kick-off Meeting (Construction) 14 Construction Inspections 15 Complete Construction / Pre-Functional Testing Checklists 16 Complete Functional Performance Testing 17 Complete O&M and Systems Manual 18 Complete Training Manual 18 Conduct Maintenance Staff Training 19 Project Completion 20 Address All Outstanding Issues and Discrepancies 20 Finalize Commissioning Report 21 Warranty Review | 3 | Commissioning Kick-off Meeting (Design) | | | | | |
| 5 Complete Schematic Design 6 Develop Draft of BOD 7 CxA Design Development Review 7 Complete Design Development 8 Complete Construction Documents 9 Pre-bid Meeting 10 Finalize Construction Contracts 11 Pre-construction Meeting 11 Start Construction 12 Review and Approve All Submittals 13 Commissioning Kick-off Meeting (Construction) 14 Construction Inspections 15 Complete Construction / Pre-Functional Testing Checklists 16 Complete Functional Performance Testing 17 Complete O&M and Systems Manual 18 Complete Training Manual 18 Conduct Maintenance Staff Training 19 Project Completion 20 Address All Outstanding Issues and Discrepancies 20 Finalize Commissioning Report 21 Warranty Review | 4 | Develop Draft of Commissioning Plan | | | | | |
| 6 Develop Draft of BOD 7 CxA Design Development Review 7 Complete Design Development 8 Complete Construction Documents 9 Pre-bid Meeting 10 Finalize Construction Contracts 11 Pre-construction Meeting 11 Start Construction 12 Review and Approve All Submittals 13 Commissioning Kick-off Meeting (Construction) 14 Construction Inspections 15 Complete Construction / Pre-Functional Testing Checklists 16 Complete Functional Performance Testing 17 Complete O&M and Systems Manual 18 Complete Training Manual 18 Conduct Maintenance Staff Training 19 Project Completion 20 Address All Outstanding Issues and Discrepancies 20 Finalize Commissioning Report 21 Warranty Review | 5 | CxA Schematic Design Review | | | | | |
| 7 CxA Design Development Review 7 Complete Design Development 8 Complete Construction Documents 9 Pre-bid Meeting 10 Finalize Construction Contracts 11 Pre-construction Meeting 11 Start Construction 12 Review and Approve All Submittals 13 Commissioning Kick-off Meeting (Construction) 14 Construction Inspections 15 Complete Construction / Pre-Functional Testing Checklists 16 Complete Functional Performance Testing 17 Complete O&M and Systems Manual 18 Complete Training Manual 18 Conduct Maintenance Staff Training 19 Project Completion 20 Address All Outstanding Issues and Discrepancies 20 Finalize Commissioning Report 21 Warranty Review | 5 | Complete Schematic Design | | | | | |
| 7 Complete Design Development 8 Complete Construction Documents 9 Pre-bid Meeting 10 Finalize Construction Contracts 11 Pre-construction Meeting 11 Start Construction 12 Review and Approve All Submittals 13 Commissioning Kick-off Meeting (Construction) 14 Construction Inspections 15 Complete Construction / Pre-Functional Testing Checklists 16 Complete Functional Performance Testing 17 Complete O&M and Systems Manual 18 Complete Training Manual 18 Conduct Maintenance Staff Training 19 Project Completion 20 Address All Outstanding Issues and Discrepancies 20 Finalize Commissioning Report 21 Warranty Review | 6 | Develop Draft of BOD | | | | | |
| 8 Complete Construction Documents 9 Pre-bid Meeting 10 Finalize Construction Contracts 11 Pre-construction Meeting 11 Start Construction 12 Review and Approve All Submittals 13 Commissioning Kick-off Meeting (Construction) 14 Construction Inspections 15 Complete Construction / Pre-Functional Testing Checklists 16 Complete Functional Performance Testing 17 Complete O&M and Systems Manual 18 Complete Training Manual 18 Conduct Maintenance Staff Training 19 Project Completion 20 Address All Outstanding Issues and Discrepancies 20 Finalize Commissioning Report 21 Warranty Review | 7 | CxA Design Development Review | | | | | |
| 9 Pre-bid Meeting 10 Finalize Construction Contracts 11 Pre-construction Meeting 11 Start Construction 12 Review and Approve All Submittals 13 Commissioning Kick-off Meeting (Construction) 14 Construction Inspections 15 Complete Construction / Pre-Functional Testing Checklists 16 Complete Functional Performance Testing 17 Complete O&M and Systems Manual 18 Complete Training Manual 18 Conduct Maintenance Staff Training 19 Project Completion 20 Address All Outstanding Issues and Discrepancies 20 Finalize Commissioning Report 21 Warranty Review | 7 | Complete Design Development | | | | | |
| Finalize Construction Contracts 11 Pre-construction Meeting 11 Start Construction 12 Review and Approve All Submittals 13 Commissioning Kick-off Meeting (Construction) 14 Construction Inspections 15 Complete Construction / Pre-Functional Testing Checklists 16 Complete Functional Performance Testing 17 Complete O&M and Systems Manual 18 Complete Training Manual 18 Conduct Maintenance Staff Training 19 Project Completion 20 Address All Outstanding Issues and Discrepancies 20 Finalize Commissioning Report 21 Warranty Review | 8 | Complete Construction Documents | | | | | |
| 11 Pre-construction Meeting 11 Start Construction 12 Review and Approve All Submittals 13 Commissioning Kick-off Meeting (Construction) 14 Construction Inspections 15 Complete Construction / Pre-Functional Testing Checklists 16 Complete Functional Performance Testing 17 Complete O&M and Systems Manual 18 Complete Training Manual 19 Project Completion 20 Address All Outstanding Issues and Discrepancies 20 Finalize Commissioning Report 21 Warranty Review | 9 | Pre-bid Meeting | | | | | |
| 11 Start Construction 12 Review and Approve All Submittals 13 Commissioning Kick-off Meeting (Construction) 14 Construction Inspections 15 Complete Construction / Pre-Functional Testing Checklists 16 Complete Functional Performance Testing 17 Complete O&M and Systems Manual 18 Complete Training Manual 18 Conduct Maintenance Staff Training 19 Project Completion 20 Address All Outstanding Issues and Discrepancies 20 Finalize Commissioning Report 21 Warranty Review | 10 | Finalize Construction Contracts | | | | | |
| 12 Review and Approve All Submittals 13 Commissioning Kick-off Meeting (Construction) 14 Construction Inspections 15 Complete Construction / Pre-Functional Testing Checklists 16 Complete Functional Performance Testing 17 Complete O&M and Systems Manual 18 Complete Training Manual 18 Conduct Maintenance Staff Training 19 Project Completion 20 Address All Outstanding Issues and Discrepancies 20 Finalize Commissioning Report 21 Warranty Review | 11 | Pre-construction Meeting | | | | | |
| Commissioning Kick-off Meeting (Construction) Construction Inspections Complete Construction / Pre-Functional Testing Checklists Complete Functional Performance Testing Complete O&M and Systems Manual Complete Training Manual Conduct Maintenance Staff Training Project Completion Address All Outstanding Issues and Discrepancies Finalize Commissioning Report Warranty Review | 11 | Start Construction | | | | | |
| 14 Construction Inspections 15 Complete Construction / Pre-Functional Testing Checklists 16 Complete Functional Performance Testing 17 Complete O&M and Systems Manual 18 Complete Training Manual 18 Conduct Maintenance Staff Training 19 Project Completion 20 Address All Outstanding Issues and Discrepancies 20 Finalize Commissioning Report 21 Warranty Review | 12 | Review and Approve All Submittals | | | | | |
| 15 Complete Construction / Pre-Functional Testing Checklists 16 Complete Functional Performance Testing 17 Complete O&M and Systems Manual 18 Complete Training Manual 18 Conduct Maintenance Staff Training 19 Project Completion 20 Address All Outstanding Issues and Discrepancies 20 Finalize Commissioning Report 21 Warranty Review | 13 | Commissioning Kick-off Meeting (Construction) | | | | | |
| 16 Complete Functional Performance Testing 17 Complete O&M and Systems Manual 18 Complete Training Manual 18 Conduct Maintenance Staff Training 19 Project Completion 20 Address All Outstanding Issues and Discrepancies 20 Finalize Commissioning Report 21 Warranty Review | 14 | Construction Inspections | | | | | |
| 17 Complete O&M and Systems Manual 18 Complete Training Manual 18 Conduct Maintenance Staff Training 19 Project Completion 20 Address All Outstanding Issues and Discrepancies 20 Finalize Commissioning Report 21 Warranty Review | 15 | Complete Construction / Pre-Functional Testing Checklists | | | | | |
| 18 Complete Training Manual 18 Conduct Maintenance Staff Training 19 Project Completion 20 Address All Outstanding Issues and Discrepancies 20 Finalize Commissioning Report 21 Warranty Review | 16 | Complete Functional Performance Testing | | | | | |
| 18 Conduct Maintenance Staff Training 19 Project Completion 20 Address All Outstanding Issues and Discrepancies 20 Finalize Commissioning Report 21 Warranty Review | 17 | Complete O&M and Systems Manual | | | | | |
| 19 Project Completion 20 Address All Outstanding Issues and Discrepancies 20 Finalize Commissioning Report 21 Warranty Review | 18 | Complete Training Manual | | | | | |
| 20 Address All Outstanding Issues and Discrepancies 20 Finalize Commissioning Report 21 Warranty Review | 18 | Conduct Maintenance Staff Training | | | | | |
| 20 Finalize Commissioning Report 21 Warranty Review | 19 | Project Completion | | | | | |
| 21 Warranty Review | 20 | Address All Outstanding Issues and Discrepancies | | | | | |
| | 20 | Finalize Commissioning Report | | | | | |
| 22 Lessons Learned Meeting | 21 | Warranty Review | | | | | |
| | 22 | Lessons Learned Meeting | | | | | |

Figure 3 Sample Cx Schedule

Program Requirements

Schedules for Cx activities are required for all commissioning plans and reports.

Commissioning Resources, and Clarifications

Issues and Resolutions Log

The Issues and Resolutions Log is the on-going list of issues, discrepancies, and questions throughout design and construction of a project that needs to be communicated to the project team for resolution or action. These are often shown in table format and supplemented with pictures and drawings where necessary. Below is an example of an acceptable Issues and Resolutions log to be included in commissioning reports.

| Issue number | Date of Issue | Issue description | Effects of issue on building operation | Possible cause of issue or problem | Recommendation for resolution | Person assigned to issue | Resolution Approval & Date | Pictures of Issue | Picture(s) of Resolution | Notes |
|-----------------|---------------------|-------------------|--|------------------------------------|-------------------------------|--------------------------------|----------------------------------|----------------------|--------------------------------|-------|
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |

Figure 4 Sample Issues and Resolution Log

Program Requirements

An Issues and Resolutions Log must be included in the final commissioning report. The log must include the descriptions of issues and the measures taken to correct them. All significant issues impacting building energy performance must be resolved prior to the approval of the commissioning report.